

Note:

- Measurements are from the centerline of closest existing track.
- Traffic Control as per OTM Book 7 Standards
- Location of any signs/traffic control devices will not obstruct sight-lines for vehicles/ pedestrians.
- 6ft Fast Fence will secure all work areas to prevent entry of commuters/passengers.
- Temporary movement of equipment & trucks will be directed with the aid of traffic control personnel.
- Swing area will remain outside the ROW.
- The Sending pit will be revised to 12m x 4m.
- The Receiving pit will be revised to 4m x 3m.





